



भारत हेवी इलेक्ट्रिकल्स लिमिटेड

(भारत सरकार का उपक्रम)

BHARAT HEAVY ELECTRICALS LIMITED

(A Govt. of India Undertaking)

TCN - 02

Ref: PSER:RKL:SCT-C003:TCN-02

Date: 22-11-2022

Sub	Tender Change Notice (TCN) - 02.	
Job	Balance work for readiness of toilets in CHP MCC-2, AHP MCC-1, Silo MCC, HCSD Pump House, Silo Utility Building & other CHP AHP area at 1x250 MW NSPCL Rourkela PP-II Expansion, Odisha.	
Ref	1.0	Tender no PSER:RKL:SCT-C003:22
	2.0	BHEL's NIT, vide reference no PSER:RKL:SCT-C003:2469, Date: 12-11-2022.
	3.0	BHEL's TCN-01, vide reference no PSER: RKL:SCT-C003:TCN-01 Date: 21-11-2022.
	4.0	Other references, if any.

With reference to above, following points/documents, relevant to tender, may please be noted and complied with while submitting the offer.

1. VOLUME-III-PRICE SCHEDULE, REV-01 is attached superseding VOLUME-III PRICE SCHEDULE, REV-00 issued earlier along with NIT. Bidder shall quote their offer accordingly.
2. Revised 'No deviation certificate' is attached. Bidder to submit 'No deviation certificate' as per attached format only.
3. All other terms & conditions shall remain unchanged.

Thanking you,

Yours faithfully,
for BHARAT HEAVY ELECTRICALS LTD.

Sr Manager (SCT-RKL)

Encl: As Above.

पावर सेक्टर पूर्वी क्षेत्र (मुख्यालय)

POWER SECTOR EASTERN REGION, DJ-9/1, SALT LAKE CITY, KOLKATA - 700 091

फैक्स/Fax : (033) 23211960

फोन/Phone : बोर्ड/EPABX : (033) 2339 8000

FORMAT FOR NO DEVIATION CERTIFICATE (REVISED)
(To be submitted in the bidder's letter head)

BHARAT HEAVY ELECTRICALS LIMITED,
 BHEL SITE OFFICE (1 x 250MW NSPCL ROURKELA TPP-III)
 ROURKELA STEEL PLANT, ROURKELA, DIST- SUNDARGARH,
 ODISHA, PIN-769011

Sub	No Deviation Certificate.	
Job	Balance work for readiness of toilets in CHP MCC-2, AHP MCC-1, Silo MCC, HCSD Pump House, Silo Utility Building & other CHP AHP area at 1x250 MW NSPCL Rourkela PP-II Expansion, Odisha.	
Ref	1.0	Tender no PSER:RKL:SCT-C003:22
	2.0	BHEL's NIT, vide reference no PSER:RKL:SCT-C003:2469, Date: 12-11-2022.
	3.0	BHEL's TCN-01, vide reference no PSER: RKL:SCT-C003:TCN-01 Date: 21-11-2022.
	4.0	BHEL's TCN-02, vide reference no PSER: RKL:SCT-C003:TCN-02 Date: 22-11-2022.
	5.0	All other pertinent issues till date.

Dear Sirs,

With reference to above, this is to confirm that as per tender conditions, we have visited site before submission of our offer and noted the job content & site conditions etc. We also confirm that we have not changed/ modified the tender documents as appeared in the website/ issued by you and in case of such observance at any stage, it shall be treated as null and void.

We hereby confirm that we have not taken any deviation from tender clauses together with other references as enumerated in the above-referred NIT. We hereby confirm our unqualified acceptance to all terms & conditions, unqualified compliance to technical specification, integrity pact (if applicable).

In the event of observance of any deviation in any part of our offer later whether implicit or explicit, the deviations shall stand null & void.

We confirm to have submitted/uploaded offer/documents in accordance with tender instructions with acceptance of the terms & conditions of the tender by us and as per aforesaid references.

Thanking you,

Yours faithfully,

(Signature, date & seal of authorized
representative of the bidder)

TCN-02	
VOLUME-III PRICE SCHEDULE (REV-01)	
Job: Balance work for readiness of toilets in CHP MCC-2,AHP MCC-1,Silo MCC,HCS D Pump House,Silo Utility Building & other CHP AHP area at 1x250 MW NSPCL Rourkela PP-II Expansion, Odisha.	
TENDER NO. PSER:RKL-SCT-C003:22	
PREAMBLE	
SL NO	DESCRIPTION
1.0	This preamble forms part of tender document and schedule of items. The tenderer should read this preamble carefully before filling in rates for various items. Clauses under this preamble shall be read in conjunction with various volumes of tender and other tender sections as applicable and shall have precedence over any contrary statement mentioned any where in this document.
2.0	The work shall be carried out strictly as per specifications, description of the items in these schedule and / or engineer's instructions. Drawings enclosed with the tender are only preliminary and for guidance/tender purposes giving some idea of the work involved. The work is to be executed as per terms & conditions of the tender and actual drawings/documents, which shall be furnished during execution.
3.0	Items of work provided in this schedule but not covered in this specification shall be executed strictly as per instruction of the engineer.
4.0	Unless specifically mentioned otherwise in the tender document, the tenderer shall quote for the finished items and shall provide for the complete cost towards power, fuel, tools, tackles, equipment, constructional plants, temporary works, labour, dismantling of all temporary piping, structures, valves, pumps, tanks & other misc. equipment, strengthening of roads/culverts/bridges etc. including arranging all clearances etc. required for carrying out different activities & tests, materials, levies, transport, layout, repairs, rectification, maintenance till handing over, supervisions, colonies, shops, establishments, overheads, profits and all incidental items not specifically mentioned but reasonably implied and necessary to complete the work according to the complete tender document and this schedule.
5.0	Prior written approval of BHEL shall be sought by the contractor in case quantity variation of any item crosses +50% (plus fifty percent) limit during execution and approval to be obtained before execution of further quantity for this item.
6.0	In case Sealed /Paper Price Bids are opened for finalisation of the tender, for any Item Rate/BOQ based service contract, possibility of variation of quantity/ addition/deletion of items can not be ruled out. Under such circumstances, after execution of work, if it is observed that standing as L-1 is changed based on actual quantity executed, the bidder shall give suitable rebate to maintain your standing as L-1. Since this aspect can be assessed at the end of execution, necessary adjustment will be effected at the end of execution in final bill.This condition shall not be applicable where the tender is finalised through Reverse Auction.

TCN-02	
VOLUME-III PRICE SCHEDULE (REV-01)	
Job: Balance work for readiness of toilets in CHP MCC-2,AHP MCC-1,Silo MCC,HCS D Pump House,Silo Utility Building & other CHP AHP area at 1x250 MW NSPCL Rourkela PP-II Expansion, Odisha.	
TENDER NO. PSER:RKL-SCT-C003:22	
PREAMBLE	
SL NO	DESCRIPTION
7.0	BHEL reserve the right to rationalize the rates, quoted by L-1 bidder against unit rate items and/ or other optional items with respect to item-wise lowest rates (amongst the participating bidders), before placement of order.The rates of unit rate/optional items shall remain valid till execution of the order, if the job/work is awarded to the bidder.
8.0	The rates quoted shall be inclusive of cleaning of site of any vegetation, dressing , clearing of old structures and leveling etc. including fixing of grid pillars, benchmarks etc. required for commencement of site activities. No separate payment will be made towards the same.However, if separate rate for such item is available in the rate schedule, the same shall be considered.
9.0	Rates shall be quoted in figures and in words in clear legible writing. No overwriting is allowed. All scoring and cancellations should be countersigned and in case of illegibility the interpretation of engineer shall be final. All entries shall be in English language.
10.0	All works item wise shall be measured upon completion and paid for at the rates quoted and accepted as per BHEL approved payment schedule/billing break-up.
11.0	The tenderer shall be deemed to have visited site and made himself aware of all the site conditions, studied the specifications and details of work to be done within the time schedule attached and to have acquainted himself of the conditions prevailing at site before submission of his bid/offer. No claim whatsoever due to lack of knowledge of site conditions shall be entertained after award of the work.
12.0	No splitting of the job is envisaged unless the same is specifically indicated in the TCC/Vol-1F. Decision of BHEL in this regard shall be final and binding to the bidders.
13.0	Bidders are not allowed to alter the Price Schedule format including item description,quantity etc. and the offer is liable for rejection if the bidders submit their prices in Price Schedules modified by them.BHEL reserves the right to reject the offers of bidders who submit offers in Price Formats which are modified/altered by them. Also putting any comments instead of rates/price in the designated column of the rate schedule shall make the offer liable for rejection.
14.0	Bidders to note that for Civil &/Structural packages, against a particular item against a ST No. appearing in more than one schedule of the BOQ, same rate must be quoted in all schedules for that particular items with same descriptions. If by error, different rates are quoted in different schedules for same ST No.(i.e. item with same description), then the higher of the rates shall be considered for evaluation but awarding shall be done with the lower rate ,if the bidder becomes L-1. The same modality shall be applicable for other item rate service contracts where item with same description is repeated in different schedules.

TCN-02	
VOLUME-III PRICE SCHEDULE (REV-01)	
Job: Balance work for readiness of toilets in CHP MCC-2,AHP MCC-1,Silo MCC,HCSD Pump House,Silo Utility Building & other CHP AHP area at 1x250 MW NSPCL Rourkela PP-II Expansion, Odisha.	
TENDER NO. PSER:RKL-SCT-C003:22	
PREAMBLE	
SL NO	DESCRIPTION
15.0	For Lumpsum Service Contract : The items/components indicated in the tender is indicative and may vary to any extent. No compensation shall be payable in case of any variation in the items/components listed in the bill of quantities if the executed weight remains within the variation limit. However, in case of deletion of any item or addition of new items over and above the items listed or variation of existing quantity beyond variation limit specified, adjustment (i.e. Payment or recovery as the case may be) shall be done on pro-rata basis based on the Rate per MT worked out from the quoted lump-sum Price and the total weight of components listed /indicated in price schedule plus 15% weight variation limit.
16.0	Engineer's decision shall be final and binding on the contractor regarding clarification of items in the schedule with respect to the other sections/volumes of the contract.
17.0	In case of tender for Civil and/or Structural works,if the Non-schedule items are not quoted by the bidder, it will be treated at par with rate of corresponding item of CPWD/PWD/DSR schedule as prescribed in the tender/BOQ cum Rate Schedule. PVC/escalation is not payable for these Non-scheduled items.
18.0	No interest, whatsoever, shall be payable by BHEL on the security deposit, any bank guarantee submitted or any amount due to successful bidder/contractor. No idling charge whatsoever (either for labour or any other resources) is payable by BHEL for any reason whatsoever.
19.0	Size and weights of various items are mentioned in the attached BOQ cum rate/price schedule/TCC/ drawing for reference purpose only & these shall not be taken into consideration for quoting/calculating amount in the rate schedule. These shall be utilised as per relevant sections of tender. Bidders shall quote for each item in the rate column, taking unit as mentioned in the quantity column. Rates shall be filled in both figures and words. Amount shall be calculated based upon these rates multiplied by the mentioned quantity for the respective items.
20.0	Bidder's Total price shall be considered for evaluation unless stated otherwise.

TCN-02			
VOLUME-III PRICE SCHEDULE (REV-01)			
Job: Balance work for readiness of toilets in CHP MCC-2,AHP MCC-1,Silo MCC,HCSD Pump House,Silo Utility Building & other CHP AHP area at 1x250 MW NSPCL Rourkela PP-II Expansion, Odisha.			
TENDER NO. PSER:RKL-SCT-C003:22			
SCHEDULE - 1: TOTAL PRICE			
SL NO	DESCRIPTION	PRICE SCHEDULE REF	TOTAL PRICE (IN INR)
1.0	TOTAL PRICE FOR Balance work for readiness of toilets in CHP MCC-2,AHP MCC-1,Silo MCC,HCSD Pump House,Silo Utility Building & other CHP AHP area at 1x250 MW NSPCL Rourkela PP-II Expansion, Odisha.	SCH 2 - PRICE BREAK UP	<u>IN FIGURES:-</u>
			<u>IN WORDS:-</u>
NOTE			
1.0	Bidder shall quote total price for SCH-2- Part only at SI No. 1 above. All other amounts / rates of each item of works in respective schedules / parts will be derived based on allocated percentages/weightages. As such, any uncalled figure/ amount noted at any other place / schedule of Volume-III will not be recknoed & will stand null & void.		
2.0	Bidder to note that total price at SI No. 1 above shall be considered for evaluation & awarding. As such grand total price should be complete in all respect for the full scope defined and considering all terms and conditions.		
3.0	Bidder's quoted total price of SCH-2 at SI. No 1 above, shall be apportioned into amount of various items of works based on allocated percentages/weightages against respective item, in respective schedules / parts. As such, bidder shall not indicate / quote any amount / rate in these schedules / parts and any amount / rate quoted against any item shall not be taken into cognizance / account and offer may be liable for rejection.		
4.0	Based on the itemwise percentages/weightages allocations, the amount for the individual items of the Bill of Quantity shall be arrived at. The rates of individual items shall be derived from the amount against each items and its quantity after rounding off to upto 2 decimal places. However, RA bill payment shall be done after rounding off the gross amount to two decimal points. Any adjustment, if required, due to such methodology, will be effected / adjusted in final bill.		
5.0	Bidders to note that this is an item rate contract. Payment shall be made for the actual quantities of work executed at the unit rate arrived at as per SI No.4 above.		
6.0	Any item as per scope of work, if not included in the price quoted above and shown separately will not be taken cognizance of and the offer shall be liable for rejection.		
7.0	Price format shall not be changed by bidder in any case and it may lead to cancellation of their offer.		
8.0	The quoted price shall be excluding GST including freight on FOR site basis.		
9.0	The quantity of items may vary during execution mainly due to actual requirement etc. The unit rates work out from the overall amount quoted & accepted by BHEL shall be considered and no separate unit rates shall be allowed. Unit rates shall be valid throughout the contract period.		

TCN-02

**VOLUME-III
PRICE SCHEDULE (REV-01)**

Job: Balance work for readiness of toilets in CHP MCC-2,AHP MCC-1,Silo MCC,HCSD Pump House,Silo Utility Building & other CHP AHP area at 1x250 MW NSPCL Rourkela PP-II Expansion, Odisha.

TENDER NO. PSER:RKL-SCT-C003:22

SCHEDULE - 2: BREAK UP

ST. NO	DESCRIPTION OF ITEM	UNIT OF MEASUREMENT	QUANTITY	WEIGHTAGE
	Earth work In excavation, backfilling and disposal including necessary men/women, materials, equipment, loading, Transporting, unloading, dewatering etc as per specification, drawing and as directed by engineer- in-charge for the following.			
101	Earth work in excavation in all types of soil including ash which can be excavated by any means including setting out, levelling, dewatering (but excluding special type of dewatering viz. well point method), shoring & strutting (wherever required), dressing the sides & bottom, all lifts, ramming/compacting the excavated bottom, stacking, disposal of surplus excavated materials within a lead upto 500 m, spreading/levelling of disposed materials etc all complete for following depths below ground level.			
a	Depth from ground level but not exceeding 2 m	CUM	499.94	0.013639933
b	Depth exceeding 2 m but not exceeding 4 m	CUM	300.00	0.010429999
200 CONCRETE WORKS				
	Providing and placing concrete work including cost of labour, materials and equipment for handling, Transporting, batching, mixing, placing, vibrating and curing, (excluding cost of centering, shuttering and reinforcement) with mechanised equipments like batching plant, transit mixer, concrete pump etc. complete as per drawing, specifications and as per direction of engineer in charge for the following.(CEMENT WILL BE SUPPLIED FREE OF COST BY BHEL AS PER TCC)			
202	Concrete of grade M10 (1 part cement, 3 part sand, 6 parts of 40 mm graded aggregate by volume) as lean concrete, levelling course , mud mat under and around foundations/floors at any depth below finished floor level etc.	CUM	50.00	0.055098398
203	Concrete of grade M15 (1 part cement, 2 part sand, 4 parts of 40 mm graded aggregate by volume) as lean concrete, levelling course , mud mat under and around foundations/floors at any depth below finished floor level etc.	CUM	30.00	0.033058507

TCN-02

**VOLUME-III
PRICE SCHEDULE (REV-01)**

Job: Balance work for readiness of toilets in CHP MCC-2,AHP MCC-1,Silo MCC,HCS D Pump House,Silo Utility Building & other CHP AHP area at 1x250 MW NSPCL Rourkela PP-II Expansion, Odisha.

TENDER NO. PSER:RKL-SCT-C003:22

SCHEDULE - 2: BREAK UP

ST. NO	DESCRIPTION OF ITEM	UNIT OF MEASUREMENT	QUANTITY	WEIGHTAGE
205	Providing and laying Design Mix cement concrete conforming to IS:456 & IS 10262-2009 for reinforced concrete works with coarse sand and graded hard stone aggregate of 20mm nominal size in foundations/substructure, grade slab, paving, drains, under floors etc at any level below finished floor level, any shape, position or thickness etc complete including use of plasticizer/ superplasticizer conforming to IS:9103 (latest) to achieve required slump in concrete all complete as per specification & drawing for the following.			
a	M25 Grade	CUM	100.00	0.111691453
300 FORM WORKS				
	Providing, fixing and removing formwork at any elevations for all structures, as per specifications and including all labour, material, scaffoldings and centering complete including pockets etc. complete as per drawing, specifications and as per direction of engineer in charge for the following.			
301	Fairface form work with good quality water proof ply wood of required thickness and smooth surface below finished ground floor level for foundations, footings, base of columns, walls, columns, pilasters, beams, mass concrete, trenches etc.	SQM	500.00	0.084384545
400 REINFORCEMENT				
405	Straightening, cutting, bending, placing in position at any level, binding in position of corrosion resistant steel -HCRM re-bars of approved make with steel of grade Fe-500 confirming to IS:1786 norms including cost of binding wire, labour, scaffolding, Transporting to & from stores etc complete all as per specifications, drawings and as directed by Engineer. (STEEL WILL BE SUPPLIED BY BHEL FREE OF COST)	MT	8.00	0.028082683
1000 BRICKWORK				
	Brickwork masonry including all labour, material, equipment, Transporting, handling, scaffolding etc. at all levels as per specification, drawings and as directed by engineer - in - charge. (CEMENT FOR BRICK WORK AND MANUFACTURE OF FLY ASH BRICKS IF MANUFACTURE AT PROJECT PREMISES WILL BE SUPPLIED FREE OF COST BY BHEL AS PER TCC)			

TCN-02

**VOLUME-III
PRICE SCHEDULE (REV-01)**

Job: Balance work for readiness of toilets in CHP MCC-2,AHP MCC-1,Silo MCC,HCSD Pump House,Silo Utility Building & other CHP AHP area at 1x250 MW NSPCL Rourkela PP-II Expansion, Odisha.

TENDER NO. PSER:RKL-SCT-C003:22

SCHEDULE - 2: BREAK UP

ST. NO	DESCRIPTION OF ITEM	UNIT OF MEASUREMENT	QUANTITY	WEIGHTAGE
1001	Providing brick work in cement mortar 1:6 (1 part cement 6 parts coarse sand) in walls, chambers etc. in thickness varying from 230mm to 460mm at all depths, places and positions below plinth including raking out joints, curing, scaffolding etc. complete excluding plastering and painting.			
a	Using fly ash Cement bricks confirming to IS 12894 with crushing strength of 75 kg/cm ²	CUM	10.00	0.018569389
1002	Providing brick work in cement mortar 1:6 (1 cement 6 coarse sand) in walls, chambers etc. in thickness 230mm at all heights, places and position above plinth including raking out joints, curing, scaffolding etc complete excluding plastering and painting.			
a	Using fly ash Cement bricks confirming to IS 12894 with crushing strength of 75 kg/cm ²	CUM	10.00	0.022338268
1003	Providing brick work in cement mortar 1:4 (1 cement 4 coarse sand) in partition walls , chambers etc. in thickness 115mm at all heights, places and position above or below plinth/graded level including providing two nos. 6 mm diameter MS bars at every third layer, raking out joints, curing, scaffolding etc complete excluding plastering and painting as per specification.			
a	Using fly ash cement bricks confirming to IS 12894 with crushing strength of 75 kg/cm ²	SQM	10.00	0.002730713
1200 CEMENT MORTAR PLASTER				
	Cement mortar plaster including making grooves wherever required including all labour, material, scaffolding, curing etc at any level as per specification, drawings and as directed by engineer - in - charge.(CEMENT WILL BE SUPPLIED FREE OF COST BY BHEL AS PER TCC)			
A1201	Providing 20mm thick plaster in two layers outside the building/boundary wall or unfair face of walls in cement mortar 1:6 on walls, finished to a smooth finish including providing 3mmx3mm size grooves at junctions of two dissimilar materials all complete.	SQM	400.00	0.041590268
A1202	Providing 15mm thick plaster inside the building/boundary wall in cement mortar 1:6 on walls finished to a smooth finish as per specification all complete.	SQM	400.00	0.035120077

TCN-02

**VOLUME-III
PRICE SCHEDULE (REV-01)**

Job: Balance work for readiness of toilets in CHP MCC-2,AHP MCC-1,Silo MCC,HCSD Pump House,Silo Utility Building & other CHP AHP area at 1x250 MW NSPCL Rourkela PP-II Expansion, Odisha.

TENDER NO. PSER:RKL-SCT-C003:22

SCHEDULE - 2: BREAK UP

ST. NO	DESCRIPTION OF ITEM	UNIT OF MEASUREMENT	QUANTITY	WEIGHTAGE
1300 FINISHES TO CONCRETE / PLASTERED SURFACES				
1304	Two or more coats of acrylic distemper of approved brand and manufacture to give an even shade including a priming coat with distemper primer complete.	SQM	300.00	0.008127151
1400 FLOORING AND SKIRTING				
1417	Providing and laying vitrified ceramic tiles of matt finish of size 600x600mm from reputed / approved manufacturer including underbed of cement mortar 1:3 with neat cement slurry etc. all complete for following.			
b	10mm thick tiles In flooring	SQM	150.00	0.053600084
d	10mm thick tiles In skirting and dado upto specific height	SQM	200.00	0.074657418
A1801	Providing and Filling in trenches, plinths, area paving and other underground structures with graded stone aggregate of size range 63 mm to 45 mm in layers not exceeding 300 mm in thickness including breaking of stone boulders to required sizes, filling the interstices with selected sand and compacting to 85 % of original volume of stone stack for all lifts etc. all complete. Payment shall be made for the measurement of the volume of the compacted fill.	CUM	50.00	0.023281248
1815	Providing and fixing GI rungs in concrete/brick walls having zinc coating of minimum 900 g/sqm etc. all complete.	Kg	40.00	0.001130271
2100 WATER SUPPLY				
	Water supply work including men, material, equipment etc. at any level as per specification, drawings and as directed by engineer - in - charge.			

TCN-02

**VOLUME-III
PRICE SCHEDULE (REV-01)**

Job: Balance work for readiness of toilets in CHP MCC-2,AHP MCC-1,Silo MCC,HCSD Pump House,Silo Utility Building & other CHP AHP area at 1x250 MW NSPCL Rourkela PP-II Expansion, Odisha.

TENDER NO. PSER:RKL-SCT-C003:22

SCHEDULE - 2: BREAK UP

ST. NO	DESCRIPTION OF ITEM	UNIT OF MEASUREMENT	QUANTITY	WEIGHTAGE
2101	Providing and fixing in position tested heavy duty type chromium plated (CP) brass long neck bib cocks including sockets, union, nuts etc all complete as per specification- 15mm nominal bore.	EACH	2.00	0.000570768
2102	Providing and fixing in position heavy duty brass stop cock of approved quality including all specials etc all complete - 15mm nominal bore.	EACH	72.00	0.014602531
2103	Providing and fixing in position heavy duty brass full way valve with wheel of approved quality including all specials etc all complete for following sizes:			
a	25mm nominal bore.	EACH	8.00	0.002521701
b	50mm nominal bore.	EACH	8.00	0.006064885
2104	Providing and fixing GI pipes class B medium class conforming to IS:1239 pipes shall be concealed and painted with anticorrosive paint, complete for internal works with GI sockets, unions, elbows, tees, nipples etc and clamps including cutting and making good the walls etc all complete for following sizes:			
a	15 mm nominal bore.	RM	50.00	0.006905107
b	20 mm nominal bore.	RM	10.00	0.001501796
c	25 mm nominal bore.	RM	50.00	0.008498875
2105	Providing and fixing GI pipes class B complete for external work with GI sockets, unions, elbows, tees, nipples etc including trenching & refilling, anti-corrosive paint etc all complete for following sizes:			
a	15 mm nominal bore.	RM	60.00	0.006648326
b	20 mm nominal bore.	RM	10.00	0.001226323

TCN-02

**VOLUME-III
PRICE SCHEDULE (REV-01)**

Job: Balance work for readiness of toilets in CHP MCC-2,AHP MCC-1,Silo MCC,HCSD Pump House,Silo Utility Building & other CHP AHP area at 1x250 MW NSPCL Rourkela PP-II Expansion, Odisha.

TENDER NO. PSER:RKL-SCT-C003:22

SCHEDULE - 2: BREAK UP

ST. NO	DESCRIPTION OF ITEM	UNIT OF MEASUREMENT	QUANTITY	WEIGHTAGE
c	25 mm nominal bore.	RM	50.00	0.007123286
d	50 mm nominal bore.	RM	25.00	0.005185011
2106	Providing and fixing 610mmx453mmx6mm thk mirror from reputed mirror manufacturer. Mirror shall be mounted with glass adjustable revolving CP brackets with CP screws etc all complete.	EACH	10.00	0.003627285
2108	Providing and fixing 25 mm diameter anodised aluminium towel rails (600mm X 25mm) all complete.	EACH	15.00	0.001889159
A2108	Providing and fixing 25 mm diameter stainless steel towel rails (600mm X 20mm) all complete.	EACH	2.00	0.000347822
2109	Providing and fixing 20mm dia chromium plated M.S. pipes wall mounted towel rod with C.P. Brackets etc all complete.	EACH	3.00	0.000447336
2110	Providing and fixing C.P. soap holder mounted with C.P. screws etc all complete.	EACH	12.00	0.002351512
2111	Providing and fixing stainless steel / C.P. liquid soap dispenser . Dispenser shall be round and easily revolving with removable threaded nozzle and mounted on C.P. brackets etc all complete.	EACH	15.00	0.002482879
2112	Providing and fixing glazed vitreous wall mounted paper holder with suitable cover cum cutter fitted with CP screws etc. sll complete.	EACH	15.00	0.002790324
2113	The shower rose shall be of heavy quality chromium plated brass with flat bottom, of diameter 100 mm or as specified with uniform perforations.	EACH	24.00	0.006126613
2114	Providing & fixing in position P.V.C. water tank of Syntex or approved equivalent including making all necessary inlet & outlet pipes, fixture, ball cocks, valves etc all complete for following capacities. GI pipes shall be paid separately under ST No. 2105.			

TCN-02

**VOLUME-III
PRICE SCHEDULE (REV-01)**

Job: Balance work for readiness of toilets in CHP MCC-2,AHP MCC-1,Silo MCC,HCSD Pump House,Silo Utility Building & other CHP AHP area at 1x250 MW NSPCL Rourkela PP-II Expansion, Odisha.

TENDER NO. PSER:RKL-SCT-C003:22

SCHEDULE - 2: BREAK UP

ST. NO	DESCRIPTION OF ITEM	UNIT OF MEASUREMENT	QUANTITY	WEIGHTAGE
a	1000 litres capacity	EACH	10.00	0.035862922
2200 SANITARY WORKS				
	Sanitary work including all labour, material, equipment etc. at any level as per specification, drawings and as directed by engineer - in - charge.			
2201	Supply and fixing glazed vitreous china Wash Basin conforming to IS:2556 part 4 of oval shape with R.S. or C.I. brackets painted white, 15mm chromium plated brass hot & cold faucets with nylon washers, chromium plated brass chain with rubber plug, 32mm chromium plated brass bottle trap and waste of standard pattern, 32mm dia chromium plated brass trap unions, plastic connection pipe with chromium plated nuts, fittings, cutting and making good the walls where required etc all complete.			
a	White	EACH	11.00	0.048667222
2202	Providing and fixing approved vitreous china laboratory sink of size 600x400x200mm conforming to IS:2556 (part-5) with R.S. or C.I. brackets, chromium plated brass chain with rubber plug 40mm, CP brass waste and 40mm CP brass trap with necessary union complete including painting the fittings, cutting and making good the wall where required etc. all complete.	EACH	5.00	0.010198639
2204	Providing and fixing colour glazed vitreous china European type water closet conforming to IS:2556 with siphon, open front solid plastic seat and plastic cover, low level 12.5 litre PVC flushing cistern (same colour as WC) with valveless fittings, necessary C.P connections etc all complete as per customer specification.			

TCN-02

**VOLUME-III
PRICE SCHEDULE (REV-01)**

Job: Balance work for readiness of toilets in CHP MCC-2,AHP MCC-1,Silo MCC,HCSD Pump House,Silo Utility Building & other CHP AHP area at 1x250 MW NSPCL Rourkela PP-II Expansion, Odisha.

TENDER NO. PSER:RKL-SCT-C003:22

SCHEDULE - 2: BREAK UP

ST. NO	DESCRIPTION OF ITEM	UNIT OF MEASUREMENT	QUANTITY	WEIGHTAGE
a	Floor mounted	EACH	11.00	0.016624768
2205	Providing and fixing colour glazed vitreous indian type Orissa pattern (580x440mm) water closet conforming to IS:2556 part 3 with all fittings including foot rests, low level 12.5 litre PVC flushing cistern with valveless fittings, necessary C.P connections etc all complete as per customer specification.	EACH	4.00	0.007655398
2206	Providing and fixing white flat back glazed vitreous china urinals of size 440x265x355 mm with photo voltaic control flushing system as per IS:2556 (part 6, section 1) with flush pipes, lead pipes, gratings, traps and necessary C.P. fittings etc. all complete as per customer specification.	EACH	12.00	0.078127424
2207	Supply, laying and jointing UPVC pipes of class 3 as per IS:4985 including bends, branches and all other necessary fittings, M.S holder bats/clamps, cutting and making good the walls and floors, jointing, testing etc all complete for following.			
b	110mm dia pipes	RM	10.00	0.001537871
c	160mm dia pipes	RM	5.00	0.001315512
2208	Providing, laying light duty non pressure NP3 class RCC pipes with collars jointed with stiff mixture of cement mortar 1:2 including testing of joints etc all complete for following.			0.000000000
a	200mm dia	RM	25.00	0.004172221
2209	Providing, laying light duty non pressure NP2 class RCC pipes with collars jointed with stiff mixture of cement mortar 1:2 including testing of joints etc complete for following.			0.000000000
a	150mm dia	RM	25.00	0.004105537

TCN-02**VOLUME-III
PRICE SCHEDULE (REV-01)**

Job: Balance work for readiness of toilets in CHP MCC-2,AHP MCC-1,Silo MCC,HCSD Pump House,Silo Utility Building & other CHP AHP area at 1x250 MW NSPCL Rourkela PP-II Expansion, Odisha.

TENDER NO. PSER:RKL-SCT-C003:22

SCHEDULE - 2: BREAK UP

ST. NO	DESCRIPTION OF ITEM	UNIT OF MEASUREMENT	QUANTITY	WEIGHTAGE
2211	Providing and fixing C.I Manhole heavy duty cover of size 600mmx450mm including frame from reputed manufacture etc. all complete.	EACH	6.00	0.023082945
2213	Providing and fixing square mouth S.W Gully trap grade 'A' complete with CI grating, brick masonry chamber and water tight CI cover with 300x300mm (inside). The weight of cover to be not less than 4.53 Kg and frame to be not less than 2.72 Kg etc all complete for following sizes:			
a	100x100mm P or S Type.	EACH	6.00	0.005353623
b	150x100mm P or S Type.	EACH	20.00	0.018285491
c	150x150mm P or S Type.	EACH	18.00	0.016833859
2215	Providing and fixing C.I. floor traps with C.P jalli all complete.	EACH	18.00	0.009771299
2219	Providing and fixing white vitreous urinal partitions of size 675x325x85mm all complete.	EACH	10.00	0.008029724
2220	Providing and fixing eye and face drinking water fountain (combined unit with receptacle conforming to IS: 10592) all complete as per specification.	EACH	5.00	0.011933602
	TOTAL			1.000000000